



* VERIFY DIMENSIONS WITH MANUFACTURER

ELECTRICAL NOTES:

- CONTRACTOR IS TO VERIFY THAT DETAIL SPECIFICATIONS AND EQUIPMENT LOCATIONS MEET WITH SERVING UTILITY'S REQUIREMENTS AND CITY OF PUYALLUP ENGINEERING REQUIREMENTS.
- METERBASE: 200 AMP, 5 JAW, AW #121314, (WITH BYPASS BLOCKS)
- PANEL BOARD: 120/240 VAC, 200 AMP, 1 PHASE, 3 WIRE, COPPER BUS WESTINGHOUSE BAB BOLT-ON BREAKERS:
 - 1 - 200/2 MAIN (200AMP/2POLE)
 - 3 - 20/2 ILLUMINATION BRANCH OR MORE IF NEEDED
- CONTRACTOR: LIGHTING RATED, 2 POLE, 120 VAC COIL
- PHOTO ELECTRIC CELL: 1800 VA, 120 VAC, ALR #SST-IES (PER WSDOT SPEC)
- PHOTO-CELL BYPASS SWITCH, SPST, 15 AMP, 277 VAC
- GROUND FAULT RECEPTACLE, 120 VAC, DUPLEX, 20 A
- SEAL CABINETS TO BASE WITH SILICON SEALANT. PLACE SEALANT ON PEDESTAL AND SET CABINETS INTO SEALANT.

CABINET: NEMA 3R, PADMOUNT, 5052 1/8" ALUMINUM CONSTRUCTION 2 SCREENED AND GASKETED VENTS
 DOORS: HEAVY DUTY CONCEALED HINGES (LIFT-OFF TYPE) STAINLESS STEEL VAULT HANDLES, PADLOCKABLE METER DOOR, BEST CX LOCK ON DISTRIBUTION DOOR, POLISHED WIRE GLASS WINDOW IN METER DOOR CLOSED CELL NEOPRENE GASKET, CARD HOLDER
 FINISH: POLYESTER POWDER COAT, ALUMINUM OUTSIDE, WHITE INSIDE

OTHER NOTES:
 PSE (OR OTHER FRANCHISE UTILITY STANDARDS) MAY CHANGE PERIODICALLY. IT IS THE CONTRACTORS RESPONSIBILITY TO ENSURE THE PROPOSED CABINET MEETS CURRENT STANDARDS.



CITY OF PUYALLUP
 OFFICE of THE CITY ENGINEER

METER CABINET (STREET LIGHTING CONTROL & TRAFFIC CONTROL)

DRAWN BY JIM ERWIN-SVOBODA	CHECKED BY TED HILL	APPROVED BY MARK PALMER	REVISED BY G HILEN	DATE REVISED: 07/01/09 XX/XX/XX XX/XX/XX XX/XX/XX	CITY STANDARD
FILE NAME F:\DWG\COMMON\STDSCITY\STDS\01_STR\01.06\01.06.05	DATE APPROVED 01/XX/2017	SCALE 1:1	01.06.05		